

Full Port
3/4" Ball Valve
Iron Pipe Thread

Full Port 3/4" Ball Valve
I.P.T.

Furnished And
Installed by Cranberry Township
12"

***All Threaded Connections ***

Existing
Water Pressure
Reducing Valve

Minimum
12" Above Floor
Where Possible

Existing
Meter

Existing
Backflow Preventer

Full Port 3/4" Ball Valve
I.P.T.

Floor

FLOW →

NOTES:

1. METER SETTING NOT TO BE OBSTRUCTED IN ANYWAY.
2. METER SETTING MUST BE COMPLETED BEFORE METER PIT WILL BE SET.
3. BACKFLOW PREVENTION DEVICE MUST BE TWP. APPROVED
4. BACKFLOW PREVENTION DEVICE INSTALLED AND MAINTINED BY OWNER.
5. PROVIDE PROPER DRAIN AT METER SETTING.
6. STRAINER IS HIGHLY RECOMMENDED UPSTREAM OF BACKFLOW PREVENTION DEVICE.
7. DEDUCT METER CANNOT BE INSTALLED MORE THAN 5FT FROM FLOOR WITHOUT PRIOR TOWNSHIP APPROVAL.
8. DEDUCT METER NOT OWNED OR MAINTAINED BY CRANBERRY TOWNSHIP.

2025 Rochester Road • Suite 400
Cranberry Township, PA 16008-0400



(724) 778-4808 • FAX (724) 778-6488

Deduct Meter Residential

REVISIONS				DRAWING
NO.	DATE	NO.	DATE	
ORIGINAL				